

PROJECT FACT SHEET:

CLEAR CREEK

STARTED: 8/20

COMPLETED: 11/20

PROJECT LEAD: NESTUCCA NESKOWIN SAND LAKE WATERSHEDS COUNCIL

PROJECT DESCRIPTION

The Nestucca River is critical spawning and rearing habitat for multiple ESA-listed stocks of salmon, as well as Coastal Cutthroat Trout and Pacific Lamprey. The Clear Creek watershed encompasses 3,700 acres with 4.4 miles of fish habitat. From its headwaters, Clear Creek passes through Siuslaw National Forest lands before entering privately managed pasture and rural residential development. The culvert proposed for replacement is on Tillamook County owned and managed Jenck Road south of the community of Cloverdale. The project culvert is the only remaining fish passage barrier on Clear Creek. Replacing this failing culvert with a bridge will restore access to over four miles of habitat.

SPECIES + INFRASTRUCTURE

Clear Creek currently provides habitat for coho salmon, and historically supported healthy populations of chum, steelhead, Chinook and cutthroat trout. Clear Creek has interactive floodplains, large cobble, significant summer flow volumes, an ideal gradient profile, an active beaver population and an abundance of high quality spawning gravel throughout the watershed.

Jenck Road is identified as a critical bypass to Highway 101. Along Highway 101 there is a natural, low elevation point where King Tides and heavy storm surges reach the highway. In the case of a natural disaster, Jenck Road, and this crossing over Clear Creek, become critical infrastructure for emergency responders to make the North – South connection with Highway 22 to the Willamette Valley and other points east.

COMPLETED SOLUTION

This culvert crossing was replaced with a 52' long concrete bridge structure with a pile-driven foundation. The streambed was reconstructed using streambed simulation methodology. This technique emulates the stream's natural bedform, including gravels and boulders, to create optimal fish habitat and passage.



BEFORE: The undersized and unstable culvert at Clear Creek and Jenck Road was the only remaining fish passage barrier, and also a local hazard during high water and King Tide events.



AFTER: The new 52' bridge allows unimpeded fish passage, and ample capacity to pass high flows and debris during storm events.

BENEFITS ACHIEVED

- Restored access to 4.4 miles of anadromous fish habitat.
- Improved sediment and large wood transport.
- Secured safe use of Jenck Road for residents, industry and emergency vehicles.
- Added to the local economy by hiring local companies for construction, engineering and documentation.



CLEAR CREEK

CULVERT REPLACEMENT

"Salmon were observed upstream of the project site just weeks after project completion!"

- Garshaw Amidi-Abraham, NNSLWC Coordinator

HIGHLY SUCCESSFUL PARTNERSHIP

The success of the Clear Creek project was largely due to the collaborative nature of Salmon SuperHwy partners involved included federal, state and county agencies, in addition to non-profits and watershed councils. Each of these entities brought a unique perspective and value to the project.

The US Forest Service provided initial site surveys, streambed simulation designs, federal permitting and technical assistance in project implementation, as well as cash contribution. The US Fish and Wildlife Service provided technical assistance, design review and cash contribution. Tillamook County Public Works (TCPW) provided design review, construction management as well as in-kind contribution in the form of construction materials. The Nestucca, Neskowin & Sand Lake Watersheds Council provided project management, state and local permitting and contracting. The Oregon Department of Fish & Wildlife provided technical assistance in project implementation. The Oregon Watershed Enhancement Board and NOAA provided significant cash contribution.

LIST OF PARTNERS: Nestucca Neskowin Sand Lake Watershed Council • US Forest Service • US Fish and Wildlife Service • Tillamook County Public Works • Oregon Watershed Enhancement Board • OR Dept. of Fish and Wildlife • National Oceanic and Atmospheric Administration

COST + FUNDING

TOTAL PROJECT COST: \$469,550

NOAA: \$36,400 USFWS: \$40,000 OWEB: \$230,000

USFS: \$25,000 plus \$20,000 in kind

TCWP: \$118,150 in kind



DURING: Local partners worked collaboratively creating a seamless plan from start to finish, keeping the project on time and budget, and the nearby landowners happy.



DURING: Aquatic species like this sculpin are contained and transferred safely out of the project area during the construction process by partners.



AFTER: The completed project allows safe passage for both native fish species as well as local, industry and emergency traffic.



CLEAR CREEK

CULVERT REPLACEMENT











